Grounding Connectors

TYPE: LI Lay-In Connector







90°C RATING (486B LISTED)

CMC® LI-S ground connectors are manufactured from high strength 6061-T6 aluminum alloy to insure both maximum strength and conductivity. They are dual rated for both copper and aluminum conductors and are electro tin plated to provide low contact resistance and protection against corrosion. They are designed for use on conduit grounding bushings. The open-faced design allows the installer to quickly lay-in the grounding conductor as a jumper to multiple conduits with no break in the ground conductor.

SECTION OF THE SECTION SECTION	SPH
	1123
	n.e.
07	
	CA

Catalog	Fig. No.	Cond. Range	Stud Size*	Dimensions, Inches		
Number	Fig. No.	AWG	Stud Size*	Н	W	L
LI-50S	1	4 - 14	0.22	0.78	0.38	1.07
LI-112S	1	1/0 - 14	0.27	1.17	0.6	1.5
LI-200S	2	3/0 - 6	0.33	1.56	0.8	2
LI-252S	2	250 - 6	0.33	1.79	0.8	2.2





U-LA Planning and Assembly Installation Manual 304

Installer responsibility

The installer is solely responsible for:


- Complying with all local or national building codes, including any that may supercede this
 manual.
- Ensuring that UniRac and other products are appropriate for the particular installations and installation environment.
- Ensuring safe installation of all electrical aspects of the PV array.




Pub 110518-2pa May 2011

© 2011 by Unirac, Inc. All rights reserved.

Figure 1. U-LA components




1. SolarMount rail— Standard or HD (heavy duty) rails support PV modules.




3. Rear cap—Attaches back horizontal pipe to vertical pipes. Includes 3/s-inch hardware: 2 U-bolts sized for pipe and 4 flange nuts, and 2 or 4 set screws.

2. Rail bracket—Attaches rail to horizontal pipes. Includes 3%-inch hardware: 1 U-bolt, 3 hexhead bolts, and 5 flange nuts.







4. Front cap—Attaches front horizontal pipe to vertical pipes and anchors upper end of north-south braces. Includes 3/8-inch hardware: 2 U-bolts and cross-brace bolt sized for pipe, 5 flange nuts, and 2 or 4 set screws.





Figure 2: Module mounting systems

Bottom mounting clip—Mounts modules in landscape mode.



Top mounting end clamp and mid clamp—Mounts modules in landscape mode.





5. Slider—Attaches lower end of north-south cross braces to rear legs. Anchors both ends of east-west braces (if employed in your installation). Includes 3/8-inch hardware: 1 cross-brace bolt sized for pipe, 1 flange nut, and 2 or 4 set screws.



6. **Cross Brace**—Provides north-south and east-west diagonal bracing. Extrusion size matches other 2- or 3-inch components.

Be prepared to cut and drill braces on the jobsite. Hole location is 1" from the end of brace along the center line.

Material specifications

Rails, caps, sliders, rail brackets, cross braces, bottom mounting clips, and top mounting clamps—6105-T5 aluminum extrusion; caps are welded.

Fasteners—304 stainless steel.

Horizontal and vertical pipe (installer supplied)—Minimum

requirement of ASTM A53B Schedule 40 galvanized steel pipe in 2" or 3" diameter.

Concrete (installer supplied)—Rated for a minimum of 2,500 pounds per square inch.

Planning the array prior to installation


On a U-LA truss structure, leg caps, rail brackets, and cross pipe couplers must be offset from one another in the east-west direction. If you are using top mounting clamps, any conflicts among these components can be dealt with easily on site, so there is never the need to deviate from the average east/west leg spacing listed on your Specs Sheet. Go on to "Lay out and excavate leg positions," below.

If you are using bottom mounting clips there is a small chance that a conflict will require you to deviate slightly from the listed average leg spacing. Make a scale drawing to identify potential component conflicts (see Fig. 3 or Fig. 4). If one occurs, use one or more of these solutions:

- Select a different set of module holes to mount your modules (an option available for bottom mounting clips only).
- Shift the position of conflicting pair of legs without exceeding maximum leg spacing listed on your Specs Sheet.
- Shift all cross pipes and rails relative to the legs without exceeding maximum cross pipe overhang listed on your Specs Sheet.


Cross pipe coupler conflicts and minor conflicts between leg caps and rail brackets, where offsets are near but not below the minimums listed in Figure 3 or 4, can be dealt with easily on site.


Figure 3.
Planning
installs
with bottom mounting clips



Create a dimensional drawing that lists overhang (A) and average leg spacing (B), which are listed under "Design Parameters" on page 2 of your Specs Sheet. Determine east-west offsets between vertical legs (dotted circles) to the module mounting holes you

intend to use. C and D depend on your specific modules. Determine your offsets $(X_1, X_2,$ etc.). If the offsets are less than the applicable minimum offset below, you will need to slightly shift leg positions. Be sure to keep within maximum allowable spacing.






Create a dimensional drawing that lists overhang (A) and average leg spacing (B), which are listed under "Design Parameters" on page 2 of your Specs Sheet. Determine east-west offsets between vertical legs (dotted circles) to the module mounting holes you intend to use. C and D depend on your specific modules. For standard rail, E equals 2C plus 5/8 inches (about 2 inches). For

HD rail, E equals C plus 1% inches (about 2% inches). Always measure the offsets

 $(X_1,X_2,$ etc.) from the farther of the two mounting holes. If the offsets are less than the applicable minimum offset below, you will need to slightly shift leg positions. Be sure to keep within maximum allowable leg spacing.



Lay out and excavate leg positions

Once the grid of leg positions has been established, verify that all angles are square.

Dig leg holes to the "Footing diameter" and "Footing depth" listed on page 2 of your Specs Sheet. If you need to promote drainage, go a few inches deeper and fill the difference with gravel.




Figure 5. North-south leg spacing is fixed. East-west spacing $(B_1, B_2, \text{etc.})$ is identical in most installations; see "Average leg spacing e-w" (Nominal Values under "Design Parameters") on page 2 of your Specs Sheet. However, if you needed to shift leg positions, follow the east-west spacing you set during your planning session.




Figure 6. A length of rebar, a threaded cap, or bolts must be installed at the foot of the vertical pipes to prevent withdrawal of the footing.



Select an assembly sequence

The assembly sequence depends on installer preference and the size of the installation. Either of these options may be followed:

- If a U-LA has just a few pairs of legs, installers may prefer to assembly the full truss structure prior to pouring concrete. Figure 7 details this approach.
- On the larger U-LA structures with many pairs of legs, installers may prefer to place the vertical leg pipes, pour the concrete, and let it cure overnight before proceeding. Figure 8 details this approach.

In either case, when mounting rails be sure to center them on the horizontal pipes, which will leave about 20 percent overhang on north and south sides.




Figure 7. FULL-TRUSS OPTION. Footing holes should extend below the frost line. You may elect to use a few inches of gravel at the base of the holes to promote drainage. Loosely assemble the full truss structure, using wood supports to stabilize vertical and horizontal pipes. When cross braces and rails are in place, square up the array and tighten fastensers. Pour concrete after array is fully assembled, save for the modules themselves. See page 8 of this manual for installation notes.




Figure 8. LEGS-FIRST OPTION. Footing holes should extend below the frost line. You may elect to use a few inches of gravel at the base of the holes to promote drainage. Using wood supports, level and square vertical leg pipes. Be certain that legs are precisely

aligned and that the front and back rows are parallel. Pour cement and allow to cure overnight before proceeding. Sighting with a laser level, transit, or string line, even the tops of the poles. See page 8 of this manual for installation notes.

Installation notes

Regardless of your assembly procedure, review these notes prior to installation and keep them handy for reference on site.

Shape concrete pillars for drainage

Slope concrete away from the legs to promote drainage. This can be done above ground or slightly below the surface. *Be sure footings extend below the frost line*.




Figure 9. Drainage options.

Don't forget your sliders!

A forgotten for misplaced sliding truss anchor can result in extensive disassembly. To avoid this needless labor, be sure that all sliders are in place and correctly oriented.

Rail assembly options for landscape mode

All three modules mounting systems facilitate assembly of rails to the truss structure prior to mounting the PV modules. Bottom mounting clips and top mounting clamps provide an additional option: full north-south rows of modules can be assembled to rails prior to mounting rails to the truss structure. This option allows prefabrication and preliminary wiring—even off site, if desired.

Recommended torques for fasteners

- Set screws for leg caps and sliders: 15 foot-pounds.
- 3%-inch serrated flange nuts for U-bolts and rail brackets: 8 foot-pounds.
- 1/4-inch module mounting hardware: 10 foot-pounds

Pipe coupler positions

Remember that cross pipe couplers need to be offset from both leg caps and rail brackets. As a general guideline, place pipe couplers one-quarter to one-third of the way between leg caps and roughly midway between rail brackets.


Minor conflicts between leg caps and rail brackets

Rail brackets, rails, and module mounts can go together in several ways. If a pair of rail brackets conflicts with leg cap positions, consult the table below. For top mounting clips, Figures 3 and 4 (pp. 4–5) illustrates the arrangements allowing the least offset between module mounting holes and leg pipe centers.

Solutions to minor conflicts between leg caps and rail brackets


Module mounting style	Solutions (employ one or more as needed)
Top mounting clamps (landscape)	Shift rail toward the end of the module, reversing (if necessary) rail bracket and rail and moving them to the other side of the leg cap.
Bottom mounting clips (landscape)*	 Move mounting clips to other side of rail (standard rail only; see Fig. 10, p. 9). Reverse rail bracket and rail, moving them to the other side of the cap. Shift rail and use module mounting holes nearest the end of the module.

^{*}Rail brackets, rails, and module mounts can be configured in several ways. Figures 3 and 4 (pp. 4–5) illustrates the arrangement that permits the least offset between rail brackets and leg caps.



Attach modules

Module mounts—bottom mounting clips (below) or top mounting clamps (p. 10) — are shipped with your rail sets. All employ $\frac{1}{4}$ -inch mounting hardware.



Top mounting clamps

Top mounting end clamps (four per north-south row) and mid clamps (two at each module abutment within a row) secure PV modules without using module mounting holes. Mounting bolts slide into the top slot of either standard or HD rail. Torque to 10 foot-pounds.





Figure 11. Top mounting employs end clamps and mid clamps . They mount via T-bolts to standard or HD rail and are not dependent on the position of module mounting holes. One inch is required between modules and rails must extend 1½ inches beyond modules on each end.





Warranty Information

See http://www.unirac.com for current warranty documents and information.



Customer Owned Parallel Generation Safety Disconnect Switch

WARNING - ELECTRICAL SHOCK HAZARD.
DO NOT TOUCH TERMINALS. TERMINALS
ON BOTH THE LINE AND LOAD SIDES MAY
BE ENERGIZED IN THE OPEN POSITION



Service is energized from two sources.

Solar system and utility grid AC operating voltage:

Maximum solar AC current:

Trinity Solar
2211 Allenwood Road
Wall, NJ 07719
732-780-3779
service@trinitysolarsystems.com

PHOTOVOLTAIC SYSTEMS

Strings
Operating Current
Operating Voltage
Max. System Voltage
Short Circuit Current



ELECTRICAL SHOCK HAZARD Do Not Touch Terminals Terminals on Both the Line

and Load Sides May Be Energized

in the Open Position.

WARNING
ELECTRIC SHOCK HAZARD
THE DC CONDUCTORS OF THIS
PHOTOVOLTAIC SYSTEM ARE
UNGROUNDED AND MAY BE
ENERGIZED

WARNING
ELECTRIC SHOCK HAZARD
IF A GROUND FAULT IS INDICATED,
NORMALLY GROUNDED
CONDUCTORS MAY BE
UNGROUNDED AND ENERGIZED