
INSTALLATION OF NEW **ROOF MOUNTED PV SOLAR SYSTEM 5883 E BONIWOOD TURN** CLINTON, MD 20735

E BONIWOOD TURN



SITE

GENERAL NOTES

- 1. THE INSTALLATION CONTRACTOR IS RESPONSIBLE FOR INSTALLING ALL EQUIPMENT AND FOLLOWING ALL DIRECTIONS AND INSTRUCTIONS CONTAINED IN THE DRAWING PACKAGE AND INFORMATION RECEIVED FROM TRINITY.
- 2. THE INSTALLATION CONTRACTOR IS RESPONSIBLE FOR INSTALLING ALL EQUIPMENT AND FOLLOWING ALL DIRECTIONS AND INSTRUCTION CONTAINED IN THE COMPLETE MANUAL
- 3. THE INSTALLATION CONTRACTOR IS RESPONSIBLE FOR READING AND LINDERSTANDING ALL DRAWINGS COMPONENT AND INVERTER MANUALS PRIOR TO INSTALLATION. THE INSTALLATION CONTRACTOR IS ALSO REQUIRED TO HAVE ALL COMPONENT SWITCHES IN THE OFF POSITION AND FUSES REMOVED PRIOR TO THE INSTALLATION OF ALL FUSES BEARING SYSTEM COMPONENTS.
- ONCE THE PHOTOVOLTAIC MODULES ARE MOUNTED, THE INSTALLATION CONTRACTOR SHOULD HAVE A MINIMUM OF ONE ELECTRICIAN WHO HAS ATTENDED A SOLAR PHOTOVOLTAIC INSTALLATION COURSE ON SITE
- 5. FOR SAFETY, IT IS RECOMMENDED THAT THE INSTALLATION CREW ALWAYS HAVE A MINIMUM OF TWO PERSONS WORKING TOGETHER AND THAT EACH OF THE INSTALLATION CREW MEMBERS BE TRAINED IN FIRST AID AND CPR.
- THIS SOLAR PHOTOVOLTAIC SYSTEM IS TO BE INSTALLED FOLLOWING THE CONVENTIONS OF THE NATIONAL ELECTRICAL CODE. ANY LOCAL CODE WHICH MAY SUPERSEDE THE NEC SHALL GOVERN
- 7. ALL SYSTEM COMPONENTS TO BE INSTALLED WITH THIS SYSTEM ARE TO BE
 "UL" LISTED. ALL EQUIPMENT WILL BE NEMA 3R OUTDOOR RATED UNLESS INDOORS.

GENERAL NOTES CONTINUED

- THE DC VOLTAGE FROM THE PANELS IS ALWAYS PRESENT AT THE DC DISCONNECT ENCLOSURE AND THE DC TERMINALS OF THE INVERTER DURING DAYLIGHT HOURS ALL PERSONS WORKING ON OR INVOLVED WITH THE PHOTOVOLTAIC SYSTEM ARE WARNED THAT THE SOLAR MODULES ARE **ENERGIZED WHENEVER THEY ARE** EXPOSED TO LIGHT.
- ALL PORTIONS OF THIS SOLAR PHOTOVOLTAIC SYSTEM SHALL BE MARKED CLEARLY IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE ARTICLE 690 & 705.
- PRIOR TO THE INSTALLATION OF THIS PHOTOVOLTAIC SYSTEM THE INSTALLATION CONTRACTOR SHALL ATTEND A PRE-INSTALLTION MEETING FOR THE REVIEW OF THE INSTALLATION PROCEDURES, SCHEDULES, SAFETY AND COORDINATION.
- PRIOR TO THE SYSTEM START UP THE INSTALLATION CONTRACTOR SHALL ASSIST IN PERFORMING ALL INITIAL HARDWARE CHECKS AND DC WIRING CONDUCTIVITY CHECKS.
- FOR THE PROPER MAINTENANCE AND ISOLATION OF THE INVERTERS REFER TO THE ISOLATION PROCEDURES IN THE
- THE LOCATION OF PROPOSED ELECTRIC
 AND TELEPHONE UTILITIES ARE SUBJECT APPROPRIATE UTILITY COMPANIES AND OWNERS.
- ALL MATERIALS, WORKMANSHIP AND CONSTRUCTION FOR THE SITE IMPROVEMENTS SHOWN HEREIN SHALL BE IN ACCORDANCE WITH:
 - A) CURRENT PREVAILING MUNICIPAL AND/OR COUNTY SPECIFICATIONS STANDARDS AND REQUIREMENTS

GENERAL NOTES CONTINUED

- B) CURRENT PREVAILING UTILITY COMPANY SPECIFICATIONS. STANDARDS, AND REQUIREMENTS THIS SET OF PLANS HAVE BEEN
- PREPARED FOR THE PURPOSE OF MUNICIPAL AND AGENCY REVIEW AND APPROVAL. THIS SET OF PLANS SHALL NOT BE UTILIZED AS CONSTRUCTION DRAWINGS UNTIL REVISED TO INDICATE "ISSUED FOR CONSTRUCTION".
- ALL INFORMATION SHOWN MUST BE CERTIFIED PRIOR TO USE FOR CONSTRUCTION ACTIVITIES

ABBREVIATIONS

AMP AMPERE ALTERNATING CURRENT AC AMP FRAME ABOVE FINISHED FLOOR ABOVE FINISHED GRADE AMERICAN WIRE GAUGE

CONDUIT (GENERIC TERM OF RACEWAY, PROVIDE AS SPECIFIED) COMBINER BOX

CIRCUIT CURRENT TRANSFORMER CU COPPER DIRECT CURRENT

DISCONNECT SWITCH DWG DRAWING ELECTRICAL SYSTEM INSTALLER FMT ELECTRICAL METALLIC TUBING FUSIBLE SWITCH

FUSE GND GROUND GFI GROUND FAULT INTERRUPTER FREQUENCY (CYCLES PER

ABBREVIATIONS CONTINUED

JUNCTION BOX THOUSAND CIRCULAR MILS KILO-VOLT AMPERE kCMIL kVA KILO-WATT kWH KILO-WATT HOUR

MCB MAIN CIRCUIT BREAKER MDP MAIN DISTRIBUTION PANEL MLO MAIN LUG ONLY

MOUNTED MTG MOUNTING NEUTRAL NATIONAL ELECTRICAL CODE NOT IN CONTRACT

NIC NO# NUMBER OVER CURRENT PROTECTION

NTS OCP P PB POLF. PULL BOX

PHASE
POLY-VINYL CHLORIDE CONDUIT PVC POWER QTY

QUANTITY RIGID GALVANIZED STEEL RGS SOLID NEUTRAL JSWBD SWITCHBOARD

TYPICAL U.O.I. UNLESS OTHERWISE INDICATED WEATHERPROOF TRANSFORMER

MOUNT 72 INCHES TO BOTTOM OF ABOVE FINISHED FLOOR OR

COVER SHEET W/ SITE INFO & GENERAL NOTES PLOT PLAN W/ DWELLING & EQUIPMENT / ELEVATION ROOF PLAN W/ MODULE LOCATIONS & DIMENSIONS ELECTRICAL 3 LINE DIAGRAM

PV SYSTEM SUMMARY

ATTACHMENT METHOD

SYSTEM SIZE : 7.125kWDC / 6kW AC HANWHA (Q.PEAK-BLK G4.1 285) SOLAREDGE INVERTER TYPE # OF ARRAYS

IRON RACK MOUNTING SYSTEM

INTERCONNECTION LINE-SIDE TAP UTILITY COMPANY

Issued / Revisions DATE DESCRIPTION

TRINITY ACCT #: 2017-01-115651

DADWAL, BALBIR KAUR

Project Address:

Project Title:

5883 E BONIWOOD TURN CLINTON, MD 20735

Drawing Title: **COVER SHEET**

Drawing Information DRAWING DATE 1/27/2017 DRAWN BY: REVISED BY:

System Information: DC SYSTEM SIZE 7.125kW AC SYSTEM SIZE: 6kW TOTAL MODULE COUNT: MODULES USED: HANWHA MODULE SPEC #: Q.PEAK-BLK G4.1 285 UTILITY COMPANY: PEPCO UTILITY ACCT #: 55022358414 UTILITY METER # NXA111235457 DEAL TYPE:

Rev. No.


Sheet





2211 Allenwood Road Wall, New Jersey 07719

www.Trinity-Solar.com

GENERAL NOTES







ARRAY CIRCUIT WIRING NOTES
1.) LICENSED ELECTRICIAN ASSUMES ALL RESPONSIBILITY
FOR DETERMINING ONSITE CONDITIONS AND
EXECUTING INSTALLATION IN ACCORDANCE WITH NEC
2014

2.) LOWEST EXPECTED AMBIENT TEMPERATURE BASED ON ASHRAE MINIMUM MEAN EXTREME DRY BULB TEMPERATURE FOR ASHRAE LOCATION MOST SIMILAR TO INSTALLATION LOCATION. LOWEST EXPECTED AMBIENT TEMP = -16°C

3.) HIGHEST CONTINUOUS AMBIENT TEMPERATURE BASED ON ASHRAE HIGHEST MONTH 2% DRY BULB TEMPERATURE FOR ASHRAE LOCATION MOST SIMILAR TO INSTALLATION LOCATION. HIGHEST CONTINUOUS TEMP = 33°C

4.) 2005 ASHRAE FUNDAMENTALS 2% DESIGN TEMPERATURES DO NOT EXCEED 47°C IN THE UNITED STATES (PALM SPRINGS, CA IS 44.1°C). FOR LESS THAN 9 CURRENT-CARRYING CONDUCTORS IN A ROOF-MOUNTED SUNLIT CONDUIT AT LEAST 0.5" ABOVE ROOF AND USING THE OUTDOOR DESIGN TEMPERATURE OF 47°C OR LESS (ALL OF UNITED STATES)

5.) PHOTOVOLTAIC POWER SYSTEMS SHALL BE PERMITTED TO OPERATE WITH UNGROUNDED PHOTOVOLTAIC SOURCE AND OUTPUT CIRCUIT AS PER NEC 690.35

6.) ALL EQUIPMENT INSTALLED OUTDOORS SHALL HAVE A **NEMA 3R** RATING

7.) ALL SOLAR SYSTEM LOAD CENTERS TO CONTAIN ONLY GENERATION CIRCUITS AND NO UNUSED POSITIONS OR LOADS

8.) PV SYSTEM CIRCUITS INSTALLED ON OR IN BUILDINGS SHALL INCLUDE A RAPID SHUTDOWN FUNCTION THAT CONTROLS SPECIFIC CONDUCTORS IN ACCORDANCE WITH NEC 690.12(1) THROUGH (5)

9.) ALL WIRE LENGTHS SHALL BE LESS THAN 100' UNLESS OTHERWISE NOTED

10.) ARRAY AND SUB ARRAY CONDUCTORS SHALL BE #10 PV WIRE TYPE RHW-2 OR EQUIVELANT AND SHALL BE PROTECTED BY CONDUIT WHERE EXPOSED TO DIRECT SUNLIGHT. SUB ARRAY CONDUIT LONGER THAN 24" SHALL CONTAIN ≤ 20 CURRENT CARYING CONDUCTORS AND WHERE EXPOSED TO DIRECT SUNLIGHT SHALL CONTAIN ≤ 9 CURRENT CARRYING CONDUCTORS.

11.) FLEXIBLE CONDUIT SHALL NOT BE INSTALLED ON ROOFTOP AND SHALL BE LIMITED TO 12" IF USED OUTDOORS

12.) WHERE TWO SOURCES FEED A BUSSBAR, ONE A UTILITY AND THE OTHER AN INVERTER, PV BACKFEED BREAKER(S) SHALL BE LOCATED OPPOSITE FROM UTILITY NEC 705.12(D)(2)(3)(b)

13.) UNGROUNDED DC CIRCUIT CONDUCTORS SHALL BE IDENTIFIED WITH THE FOLLOWING OUTER FINISH: POSITIVE CONDUCTORS = RED NEGATIVE CONDUCTORS = BLACK NEC 210.5(C)(2)

CALCULATIONS FOR CURRENT CARRYING CONDUCTORS
REQUIRED CONDUCTOR AMPACITY PER STRING
[NEC 690.8(B)(1)]: (15.00*1.25)1 = 18.75A

AWG #10, DERATED AMPACITY
AMBIENT TEMP: 33°C, TEMP DERATING FACTOR: .96
RACEWAY DERATING = 4 CCC: 0.80
(40*.96)0.80 = 30.72A

30.72A [>] 18.75A, THEREFORE WIRE SIZE IS VALID

TOTAL AC REQUIRED CONDUCTOR AMPACITY 25.00A*1.25 = 31.25A

AWG #8, DERATED AMPACITY AMBIENT TEMP: 30°C, TEMP DERATING: 1.0 RACEWAY DERATING S CC: N/A 55A*1.0 = 55A


 $55A\,{}^>_-\,31.25A$, Therefore AC Wire Size is valid

CALCULATION FOR PV OVERCURRENT PROTECTION TOTAL INVERTER CURRENT: 25.00A

25.00A*1.25 = 31.25A
--> 40A OVERCURRENT PROTECTION IS VALID

SOLAR MODULES MOUNTED TO ROOF ON 2 ARRAYS 25 - 285W MODULES W/ 1 SOLAR EDGE P300 PER MODULE 15 ADC MAX PER STRING


1 STRING OF 17 MODULES IN SERIES - 350 Vmax 1 STRING OF 8 MODULES IN SERIES - 350 Vmax *2 STRINGS TO BE TERMINATED IN PARALLEL INSIDE INVERTER 1



8"x8"

JUNCTION

BOX





| | PV MODULE SPECIFICATIONS | |
|-----|------------------------------|-------|
| | HANWHA (Q.PEAK-BLK G4.1 285) | |
| Imp | | 8.98 |
| Vmp | | 31.73 |
| Voc | | 38.91 |
| Isc | | 9.56 |

| INVERTER #1 - SE6000A-US000NNR2 | | | | |
|---------------------------------|-----|---------|-------|--|
| DC | | | AC | |
| Imp | 18 | Pout | 6000 | |
| Vmp | 350 | Imax | 25 | |
| Voc | 500 | OCPDmin | 31.25 | |
| Isc | 30 | Vnom | 240 | |

NOTE: CONDUIT TYPE SHALL BE CHOSEN BY THE INSTALLATION CONTRACTOR TO MEET OR EXCEED NEC AND LOCAL AHID REQUIREMENTS

| Α | #6 THWN-2 GEC TO EXISTING GROUND ROD | |
|---|--|--|
| В | 3/4" CONDUIT W/ 2-#8 THWN-2, 1-#10 THWN-2, 1-#10 THWN-2 GROUND | |
| С | 3/4" CONDUIT W/ 4-#10 THWN-2, 1-#10 THWN-2 GROUND | |
| D | 3/4" CONDUIT W/ 4-#10 THWN-2, 1-#10 THWN-2 GROUND | |
| Е | 3/4" CONDUIT W/ 2-#8 THWN-2, 1-#10 THWN-2, 1-#10 THWN-2 GROUND | |
| F | #10 PV WIRE (FREE AIR) W/ #6 BARE COPPER BOND TO ARRAY | |
| | | |





| Issued / Revisions | | |
|--------------------|-------------------------------|-----------|
| | | |
| | | |
| | | |
| P1 | ISSUED TO TOWNSHIP FOR PERMIT | 1/27/2017 |
| NO. | DESCRIPTION | DATE |

Project Title:

DADWAL, BALBIR KAUR

TRINITY ACCT #: 2017-01-115651

Project Address:

5883 E BONIWOOD TURN CLINTON, MD 20735

Drawing Title:

PROPOSED PV SOLAR SYSTEM

| Drawing Information | | |
|---------------------|-----------|--|
| DRAWING DATE: | 1/27/2017 | |
| DRAWN BY: | JC | |
| REVISED BY: | | |
| | | |

| System Information: | |
|---------------------|---------------------|
| DC SYSTEM SIZE: | 7.125kW |
| AC SYSTEM SIZE: | 6kW |
| TOTAL MODULE COUNT: | 25 |
| MODULES USED: | HANWHA |
| MODULE SPEC #: | Q.PEAK-BLK G4.1 285 |
| UTILITY COMPANY: | PEPCO |
| UTILITY ACCT #: | 55022358414 |
| UTILITY METER #: | NXA111235457 |
| DEAL TYPE: | IGS |
| | |



PV - 5

Sheet



2211 Allenwood Road Wall, New Jersey 07719

877-797-2978 www.Trinity-Solar.com