
INSTALLATION OF NEW **ROOF MOUNTED PV SOLAR SYSTEM** 16 COLLINS LN, SEWELL, NJ 08080

COLLINS LN.



GENERAL NOTES

- 1. THE INSTALLATION CONTRACTOR IS RESPONSIBLE FOR INSTALLING ALL EQUIPMENT AND FOLLOWING ALL DIRECTIONS AND INSTRUCTIONS CONTAINED IN THE DRAWING PACKAGE AND INFORMATION RECEIVED FROM TRINITY.
- 2. THE INSTALLATION CONTRACTOR IS RESPONSIBLE FOR INSTALLING ALL EQUIPMENT AND FOLLOWING ALL DIRECTIONS AND INSTRUCTION CONTAINED IN THE COMPLETE MANUAL.
- 3. THE INSTALLATION CONTRACTOR IS RESPONSIBLE FOR READING AND LINDERSTANDING ALL DRAWINGS COMPONENT AND INVERTER MANUALS PRIOR TO INSTALLATION. THE INSTALLATION CONTRACTOR IS ALSO REQUIRED TO HAVE ALL COMPONENT SWITCHES IN THE OFF POSITION AND FUSES REMOVED PRIOR TO THE INSTALLATION OF ALL FUSE BEARING SYSTEM COMPONENTS.
- ONCE THE PHOTOVOLTAIC MODULES ARE MOUNTED, THE INSTALLATION CONTRACTOR SHOULD HAVE A MINIMUM OF ONE ELECTRICIAN WHO HAS ATTENDED A SOLAR PHOTOVOLTAIC INSTALLATION COURSE ON SITE
- 5. FOR SAFETY, IT IS RECOMMENDED THAT THE INSTALLATION CREW ALWAYS HAVE A MINIMUM OF TWO PERSONS WORKING TOGETHER AND THAT EACH OF THE INSTALLATION CREW MEMBERS BE TRAINED IN FIRST AID AND CPR.
- THIS SOLAR PHOTOVOLTAIC SYSTEM IS TO BE INSTALLED FOLLOWING THE CONVENTIONS OF THE NATIONAL ELECTRICAL CODE. ANY LOCAL CODE WHICH MAY SUPERSEDE THE NEC SHALL GOVERN
- 7. ALL SYSTEM COMPONENTS TO BE INSTALLED WITH THIS SYSTEM ARE TO BE
 "UL" LISTED. ALL EQUIPMENT WILL BE NEMA 3R OUTDOOR RATED UNLESS INDOORS.

GENERAL NOTES CONTINUED

- THE DC VOLTAGE FROM THE PANELS IS ALWAYS PRESENT AT THE DC DISCONNECT ENCLOSURE AND THE DC TERMINALS OF THE INVERTER DURING DAYLIGHT HOURS ALL PERSONS WORKING ON OR INVOLVED WITH THE PHOTOVOLTAIC SYSTEM ARE WARNED THAT THE SOLAR MODULES ARE **ENERGIZED WHENEVER THEY ARE** EXPOSED TO LIGHT.
- ALL PORTIONS OF THIS SOLAR PHOTOVOLTAIC SYSTEM SHALL BE MARKED CLEARLY IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE ARTICLE 690 & 705.
- PRIOR TO THE INSTALLATION OF THIS PHOTOVOLTAIC SYSTEM. THE INSTALLATION CONTRACTOR SHALL ATTEND A PRE-INSTALLTION MEETING FOR THE REVIEW OF THE INSTALLATION PROCEDURES, SCHEDULES, SAFETY AND COORDINATION.
- PRIOR TO THE SYSTEM START UP THE INSTALLATION CONTRACTOR SHALL ASSIST IN PERFORMING ALL INITIAL HARDWARE CHECKS AND DC WIRING CONDUCTIVITY CHECKS.
- FOR THE PROPER MAINTENANCE AND ISOLATION OF THE INVERTERS REFER TO THE ISOLATION PROCEDURES IN THE
- THE LOCATION OF PROPOSED ELECTRIC
 AND TELEPHONE UTILITIES ARE SUBJECT APPROPRIATE UTILITY COMPANIES AND OWNERS.
- ALL MATERIALS, WORKMANSHIP AND CONSTRUCTION FOR THE SITE IMPROVEMENTS SHOWN HEREIN SHALL BE IN ACCORDANCE WITH:
 - A) CURRENT PREVAILING MUNICIPAL AND/OR COUNTY SPECIFICATIONS STANDARDS AND REQUIREMENTS

GENERAL NOTES CONTINUED

- B) CURRENT PREVAILING UTILITY COMPANY SPECIFICATIONS. STANDARDS, AND REQUIREMENTS
- THIS SET OF PLANS HAVE BEEN PREPARED FOR THE PURPOSE OF MUNICIPAL AND AGENCY REVIEW AND APPROVAL. THIS SET OF PLANS SHALL NOT BE UTILIZED AS CONSTRUCTION DRAWINGS UNTIL REVISED TO INDICATE "ISSUED FOR CONSTRUCTION".
- ALL INFORMATION SHOWN MUST BE CERTIFIED PRIOR TO USE FOR CONSTRUCTION ACTIVITIES

ABBREVIATIONS

AMP

AC ALTERNATING CURRENT AMP FRAME ABOVE FINISHED FLOOR ABOVE FINISHED GRADE

AMPERE

AMERICAN WIRE GAUGE CONDUIT (GENERIC TERM OF RACEWAY, PROVIDE AS SPECIFIED) COMBINER BOX

CIRCUIT CURRENT TRANSFORMER CU COPPER DIRECT CURRENT

DISCONNECT SWITCH DWG DRAWING ELECTRICAL SYSTEM INSTALLER EMT ELECTRICAL METALLIC TUBING

FS FUSIBLE SWITCH FUSE GND GROUND

GFI GROUND FAULT INTERRUPTER FREQUENCY (CYCLES PER

ABBREVIATIONS CONTINUED

JUNCTION BOX THOUSAND CIRCULAR MILS KILO-VOLT AMPERE kVA KILO-WATT kWH KILO-WATT HOUR

MCB MAIN CIRCUIT BREAKER MAIN DISTRIBUTION PANEL MAIN LUG ONLY MDP MLO MOUNTED

MTG MOUNTING NEUTRAL NATIONAL ELECTRICAL CODE NIC NO# NOT IN CONTRACT

NUMBER NTS OCP P PB OVER CURRENT PROTECTION

POLF. PULL BOX

PHASE
POLY-VINYL CHLORIDE CONDUIT PVC QTY QUANTITY RIGID GALVANIZED STEEL


RGS SOLID NEUTRAL JSWBD SWITCHBOARD TYPICAL

UNLESS OTHERWISE INDICATED WEATHERPROOF TRANSFORMER

MOUNT 72 INCHES TO BOTTOM OF ABOVE FINISHED FLOOR OR

SHEET INDEX

- PV-1 COVER SHEET W/ SITE INFO & NOTES
- PV-2 ROOF PLAN W/ MODULE LOCATIONS
- PV-3 SITE PLAN
- **ELECTRICAL 3 LINE DIAGRAM**
- **APPENDIX**



Issued / Revisions			
P1	ISSUED TO TOWNSHIP FOR PERMIT	12/20/2017	
NO.	DESCRIPTION	DATE	

LAMONACA, WILLIAM

Project Title:

SITE

TRINITY ACCT #: 2017-12-215950

Project Address:

16 COLLINS LN, SEWELL, NJ 08080

Drawing Title:

PROPOSED PV SOLAR SYSTEM


Drawing Informatio	n
DRAWING DATE:	12/20/2017
DRAWN BY:	КВ
REVISED BY:	

System Information:		
DC SYSTEM SIZE:	15.635kW	
AC SYSTEM SIZE:	12.6kW	
TOTAL MODULE COUNT:	53	
MODULES USED:	HANWHA 295	
MODULE SPEC #:	Q.PEAK-BLK G4.1 295	
UTILITY COMPANY:	ACE	
UTILITY ACCT #:	5500 0168 041	
UTILITY METER #:	99G066709584	
DEAL TYPE:	IGS	
İ		





GENERAL NOTES



NDICATES NEW PV SOLAR MODULE. RED MODULES

INDICATE PANELS THAT USE MICRO INVERTERS.

REFER TO EQUIPMENT SCHEDULE FOR SPECS.

INDICATES NEW PRODUCTION METER TO BE

REFER TO EQUIPMENT SCHEDULE FOR SPECS.

INDICATES NEW INVERTER TO BE

INSTALLED OUTSIDE.

INSTALLED OUTSIDE

M

D

ARRAY ORIENTATION = 270°


MODULE PITCH = 18°

INDICATES EXISTING METER LOCATION

INDICATES EXISTING ELECTRICAL PANEL

INDICATES NEW MAIN DISCONNECT

LOCATION: INSIDE



SE7600H-US000NNC2

SE5000H-US000NNC2

OTHER OBSTRUCTIONS

Issued / Revisions

DESCRIPTION

16 COLLINS LN, SEWELL, NJ 08080

12/20/2017

15.635kW

HANWHA 295


5500 0168 041


99G066709584


Q.PEAK-BLK G4.1 295

12.6kW

DATE







	Issued / Revisions				
P1	ISSUED TO TOWNSHIP FOR PERMIT	12/20/2017			
NO.	DESCRIPTION	DATE			

Project Title:

LAMONACA, WILLIAM

TRINITY ACCT #: 2017-12-215950

Project Address:

16 COLLINS LN, SEWELL, NJ 08080

Drawing Title:

PROPOSED PV SOLAR SYSTEM

Drawing Information		
DRAWING DATE:	12/20/2017	
DRAWN BY:	КВ	
REVISED BY:		

System Information:		
DC SYSTEM SIZE:	15.635kW	
AC SYSTEM SIZE:	12.6kW	
TOTAL MODULE COUNT:	53	
MODULES USED:	HANWHA 295	
MODULE SPEC #:	Q.PEAK-BLK G4.1 295	
UTILITY COMPANY:	ACE	
UTILITY ACCT #:	5500 0168 041	
UTILITY METER #:	99G066709584	
DEAL TYPE:	IGS	

Rev. No.

Р

PV - :

Sheet



2211 Allenwood Road 877-797-2978 Wall, New Jersey 07719 ARRAY CIRCUIT WIRING NOTES

1.) LICENSED ELECTRICIAN ASSUMES ALL RESPONSIBILITY
FOR DETERMINING ONSITE CONDITIONS AND
EXECUTING INSTALLATION IN ACCORDANCE WITH NEC
2014

2.) LOWEST EXPECTED AMBIENT TEMPERATURE BASED ON ASHRAE MINIMUM MEAN EXTREME DRY BULB TEMPERATURE FOR ASHRAE LOCATION MOST SIMILAR TO INSTALLATION LOCATION. LOWEST EXPECTED AMBIENT TEMP = -16°C

3.) HIGHEST CONTINUOUS AMBIENT TEMPERATURE BASED ON ASHRAE HIGHEST MONTH 2% DRY BULB TEMPERATURE FOR ASHRAE LOCATION MOST SIMILAR TO INSTALLATION LOCATION. HIGHEST CONTINUOUS TEMP = 33°C

4.) 2005 ASHRAE FUNDAMENTALS 2% DESIGN TEMPERATURES DO NOT EXCEED 47°C IN THE UNITED STATES (PALM SPRINGS, CA IS 44.1°C). FOR LESS THAN 9 CURRENT-CARRYING CONDUCTORS IN A ROOF-MOUNTED SUNLIT CONDUIT AT LEAST 0.5" ABOVE ROOF AND USING THE OUTDOOR DESIGN TEMPERATURE OF 47°C OR LESS (ALL OF UNITED STATES)

5.) PV SYSTEM CIRCUITS INSTALLED ON OR IN BUILDINGS SHALL INCLUDE A RAPID SHUTDOWN FUNCTION THAT CONTROLS SPECIFIC CONDUCTORS IN ACCORDANCE WITH NEC 690.12(1) THROUGH (5)

6.) PHOTOVOLTAIC POWER SYSTEMS SHALL BE PERMITTED TO OPERATE WITH UNGROUNDED PHOTOVOLTAIC SOURCE AND OUTPUT CIRCUIT AS PER NEC 690.35

7.) UNGROUNDED DC CIRCUIT CONDUCTORS SHALL BE IDENTIFIED WITH THE FOLLOWING OUTER FINISH: POSITIVE CONDUCTORS = RED NEGATIVE CONDUCTORS = BLACK NEC 210.5(C)(2)

8.) ARRAY AND SUB ARRAY CONDUCTORS SHALL BE #10 PV WIRE TYPE RHW-2 OR EQUIVELANT AND SHALL BE PROTECTED BY CONDUIT WHERE EXPOSED TO DIRECT SUNLIGHT. SUB ARRAY CONDUIT LONGER THAN 24" SHALL CONTAIN ≤ 20 CURRENT CARYING CONDUCTORS AND WHERE EXPOSED TO DIRECT SUNLIGHT SHALL CONTAIN ≤ 9 CURRENT CARRYING CONDUCTORS.

9.) ALL WIRE LENGTHS SHALL BE LESS THAN 100' UNLESS OTHERWISE NOTED

10.) FLEXIBLE CONDUIT SHALL NOT BE INSTALLED ON ROOFTOP AND SHALL BE LIMITED TO 12" IF USED OUTDOORS

11.)OVERCURRENT PROTECTION FOR CONDUCTORS CONNECTED TO THE SUPPLY SIDE OF A SERVICE SHALL BE LOCATED WITHIN 10' OF THE POINT OF CONNECTION NEC 705 31

12.) WHERE TWO SOURCES FEED A BUSSBAR, ONE A UTILITY AND THE OTHER AN INVERTER, PV BACKFEED BREAKER(S) SHALL BE LOCATED OPPOSITE FROM UTILITY NEC 705.12(D)(2)(3)(b)

13.) ALL SOLAR SYSTEM LOAD CENTERS TO CONTAIN ONLY GENERATION CIRCUITS AND NO UNUSED POSITIONS OR LOADS

14.) ALL EQUIPMENT INSTALLED OUTDOORS SHALL HAVE A NEMA 3R RATING

CALCULATIONS FOR CURRENT CARRYING CONDUCTORS
REQUIRED CONDUCTOR AMPACITY PER STRING
[NEC 690.8(B)(1)]: (15.00*1.25)1 = 18.75A

AWG #8, DERATED AMPACITY
AMBIENT TEMP: 33°C, TEMP DERATING FACTOR: .96
RACEWAY DERATING = 10 CCC: 0.50
(55*.96)0.50 = 26.40A

26.40A - 18.75A, THEREFORE WIRE SIZE IS VALID

TOTAL AC REQUIRED CONDUCTOR AMPACITY 53.00A*1.25 = 66.25A

AWG #4, DERATED AMPACITY AMBIENT TEMP: 30°C, TEMP DERATING: 1.0 RACEWAY DERATING 5 CCC: N/A 95A*1.0 = 95A

95A $\stackrel{\scriptstyle >}{_{\sim}}$ 66.25A, THEREFORE AC WIRE SIZE IS VALID

CALCULATION FOR PV OVERCURRENT PROTECTION TOTAL INVERTER CURRENT: 53.00A

53.00A*1.25 = 66.25A
--> 70A OVERCURRENT PROTECTION IS VALID


SOLAR MODULES MOUNTED TO ROOF ON 2 ARRAYS 53 - 295W MODULES W/ 1 SOLAR EDGE P300 PER MODULE

2 STRINGS OF 11 MODULES IN SERIES - 350 Vmax 1 STRING OF 10 MODULES IN SERIES - 350 Vmax *3 STRINGS TO BE TERMINATED IN PARALLEL INSIDE INVERTER 1

1 STRING OF 11 MODULES IN SERIES - 350 Vmax 1 STRING OF 10 MODULES IN SERIES - 350 Vmax *2 STRINGS TO BE TERMINATED IN PARALLEL INSIDE INVERTER 2

EXISTING

1Ø 120/240V



).PEAK-BLK G4.1 295)			
HANWHA 295 (Q.PEAK-BLK G4.1 295)			
Imp 9.17			
32.19			
39.48			
9.7			

INVERTER #1 - SE7600H-US000NNC2		1	INVERTER #2 - SE5000H-US000NN				
С	Д	ıC .	1		oc oc	A	AC.
23	Pout	7600	1	lmp	15.5	Pout	500
400	Imax	32	1	Vmp	380	lmax	21
480	OCPDmin	40]	Voc	480	OCPDmin	26.
45	Vnom	240		Isc	30	Vnom	240
	23 400 480	23 Pout 400 Imax 480 OCPDmin	C AC 23 Pout 7600 400 Imax 32 480 OCPDmin 40	23 Pout 7600 400 Imax 32 480 OCPDmin 40	C AC Imp 23 Pout 7600 Imp 400 Imax 32 Vmp 480 OCPDmin 40 Voc	C AC DC 23 Pout 7600 Imp 15.5 400 Imax 32 Vmp 380 480 OCPDmin 40 Voc 480	C AC DC AC 23 Pout 7600 Imp 15.5 Pout 400 Imax 32 Vmp 380 Imax 480 OCPDmin 40 Voc 480 OCPDmin

NOTE: CONDUIT TYPE SHALL BE CHOSEN BY THE INSTALLATION CONTRACTOR TO MEET OR EXCEED NEC AND LOCAL AHJD REQUIREMENTS

000000

SQUARE D

PN: D222N

EXISTING MAIN BREAKER LOAD CENTER


INSULATED LINE TAPS INSTALLED ON


MAIN FEEDERS

NEC 705.12(A)

Α	#6 THWN-2 GEC TO EXISTING GROUND ROD	G	3/4" CONDUIT W/ 2-#10 THWN-2, 1-#10 THWN-2, 1-#10 THWN-2 GROUND
В	1" CONDUIT W/ 2-#4 THWN-2, 1-#8 THWN-2, 1-#8THWN-2 GROUND	I	#10 PV WIRE (FREE AIR) W/ #6 BARE COPPER BOND TO ARRAY
С	1" CONDUIT W/ 10-#10 THWN-2, 1-#10 THWN-2 GROUND	_	1" CONDUIT W/ 3-#4 THWN-2, 1-#8 THWN-2 GROUND
D	3/4" CONDUIT W/ 6-#10 THWN-2, 1-#10 THWN-2 GROUND		
Е	3/4" CONDUIT W/ 4-#10 THWN-2, 1-#10 THWN-2 GROUND		
F	3/4" CONDUIT W/ 2-#8 THWN-2, 1-#10 THWN-2, 1-#10 THWN-2 GROUND		

В





	Issued / Revisions				
P1	ISSUED TO TOWNSHIP FOR PERMIT	12/20/2017			
NO.	DESCRIPTION	DATE			

Project Title:

LAMONACA, WILLIAM

TRINITY ACCT #: 2017-12-215950

Project Address:

16 COLLINS LN, SEWELL, NJ 08080

Drawing Title:

PROPOSED PV SOLAR SYSTEM

	Drawing Information				
Drawing Informa					
DRAWING DATE:	12/20/2017				
DRAWN BY:	КВ				
REVISED BY:					

System Information:		
DC SYSTEM SIZE:	15.635kW	
AC SYSTEM SIZE:	12.6kW	
TOTAL MODULE COUNT:	53	
MODULES USED:	HANWHA 295	
MODULE SPEC #:	Q.PEAK-BLK G4.1 295	
UTILITY COMPANY:	ACE	
UTILITY ACCT #:	5500 0168 041	
UTILITY METER #:	99G066709584	
DEAL TYPE:	IGS	



PV - 4

Sheet



2211 Allenwood Road 877-797-2978 Wall, New Jersey 07719