

# INSTALLATION OF NEW ROOF MOUNTED PV SOLAR SYSTEM


## 146 FERNWOOD TERRACE LINDEN, NJ 07036

FERNWOOD TERRACE ●



VICINITY MAP  
SCALE: NTS

SITE



### Issued / Revisions

| R1  | SYSTEM SIZE DECREASE / INVERTER CHANGE / LAYOUT REVISION | 6/5/2017  |
|-----|--|-----------|
| P1  | ISSUED TO TOWNSHIP FOR PERMIT                            | 5/24/2017 |
| NO. | DESCRIPTION  | DATE      |

Project Title:

NADELLA, MICHELLE

TRINITY ACCT #: 2017-04-135521

Project Address:

146 FERNWOOD TERRACE  
LINDEN, NJ 07036

Drawing Title:

PROPOSED PV SOLAR SYSTEM

Drawing Information

|               |           |
|---------------|-----------|
| DRAWING DATE: | 5/24/2017 |
| DRAWN BY:     | RIOS      |
| REVISED BY:   | DMR       |

System Information:

|                     |                     |
|---------------------|---------------------|
| DC SYSTEM SIZE:     | 6.09kW              |
| AC SYSTEM SIZE:     | 5kW                 |
| TOTAL MODULE COUNT: | 21                  |
| MODULES USED:       | HANWHA 290          |
| MODULE SPEC #:      | Q.PEAK-BLK G4.1 290 |
| UTILITY COMPANY:    | PSE&G               |
| UTILITY ACCT #:     | 7278909902          |
| UTILITY METER #:    | 1614925             |
| DEAL TYPE:          | SUNRUN              |

Rev. No.

R1

Sheet

PV - 1



2211 Allenwood Road  
Wall, New Jersey 07719

877-797-2978  
www.Trinity-Solar.com

### GENERAL NOTES

1. THE INSTALLATION CONTRACTOR IS RESPONSIBLE FOR INSTALLING ALL EQUIPMENT AND FOLLOWING ALL DIRECTIONS AND INSTRUCTIONS CONTAINED IN THE DRAWING PACKAGE AND INFORMATION RECEIVED FROM TRINITY.
2. THE INSTALLATION CONTRACTOR IS RESPONSIBLE FOR INSTALLING ALL EQUIPMENT AND FOLLOWING ALL DIRECTIONS AND INSTRUCTION CONTAINED IN THE COMPLETE MANUAL.
3. THE INSTALLATION CONTRACTOR IS RESPONSIBLE FOR READING AND UNDERSTANDING ALL DRAWINGS, COMPONENT AND INVERTER MANUALS PRIOR TO INSTALLATION. THE INSTALLATION CONTRACTOR IS ALSO REQUIRED TO HAVE ALL COMPONENT SWITCHES IN THE OFF POSITION AND FUSES REMOVED PRIOR TO THE INSTALLATION OF ALL FUSE BEARING SYSTEM COMPONENTS.
4. ONCE THE PHOTOVOLTAIC MODULES ARE MOUNTED, THE INSTALLATION CONTRACTOR SHOULD HAVE A MINIMUM OF ONE ELECTRICIAN WHO HAS ATTENDED A SOLAR PHOTOVOLTAIC INSTALLATION COURSE ON SITE.
5. FOR SAFETY, IT IS RECOMMENDED THAT THE INSTALLATION CREW ALWAYS HAVE A MINIMUM OF TWO PERSONS WORKING TOGETHER AND THAT EACH OF THE INSTALLATION CREW MEMBERS BE TRAINED IN FIRST AID AND CPR.
6. THIS SOLAR PHOTOVOLTAIC SYSTEM IS TO BE INSTALLED FOLLOWING THE CONVENTIONS OF THE NATIONAL ELECTRICAL CODE. ANY LOCAL CODE WHICH MAY SUPERSEDE THE NEC SHALL GOVERN.
7. ALL SYSTEM COMPONENTS TO BE INSTALLED WITH THIS SYSTEM ARE TO BE "UL" LISTED. ALL EQUIPMENT WILL BE NEMA 3R OUTDOOR RATED UNLESS INDOORS.

### GENERAL NOTES

IF ISSUED DRAWING IS MARKED WITH A REVISION CHARACTER OTHER THAN "A", PLEASE BE ADVISED THAT FINAL EQUIPMENT AND/OR SYSTEM CHARACTERISTICS ARE SUBJECT TO CHANGE DUE TO AVAILABILITY OF EQUIPMENT.

### GENERAL NOTES CONTINUED

8. THE DC VOLTAGE FROM THE PANELS IS ALWAYS PRESENT AT THE DC DISCONNECT ENCLOSURE AND THE DC TERMINALS OF THE INVERTER DURING DAYLIGHT HOURS. ALL PERSONS WORKING ON OR INVOLVED WITH THE PHOTOVOLTAIC SYSTEM ARE WARNED THAT THE SOLAR MODULES ARE ENERGIZED WHENEVER THEY ARE EXPOSED TO LIGHT.
9. ALL PORTIONS OF THIS SOLAR PHOTOVOLTAIC SYSTEM SHALL BE MARKED CLEARLY IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE ARTICLE 690 & 705.
10. PRIOR TO THE INSTALLATION OF THIS PHOTOVOLTAIC SYSTEM, THE INSTALLATION CONTRACTOR SHALL ATTEND A PRE-INSTALLTION MEETING FOR THE REVIEW OF THE INSTALLATION PROCEDURES, SCHEDULES, SAFETY AND COORDINATION.
11. PRIOR TO THE SYSTEM START UP THE INSTALLATION CONTRACTOR SHALL ASSIST IN PERFORMING ALL INITIAL HARDWARE CHECKS AND DC WIRING CONDUCTIVITY CHECKS.
12. FOR THE PROPER MAINTENANCE AND ISOLATION OF THE INVERTERS REFER TO THE ISOLATION PROCEDURES IN THE OPERATION MANUAL.
13. THE LOCATION OF PROPOSED ELECTRIC AND TELEPHONE UTILITIES ARE SUBJECT TO FINAL APPROVAL OF THE APPROPRIATE UTILITY COMPANIES AND OWNERS.
14. ALL MATERIALS, WORKMANSHIP AND CONSTRUCTION FOR THE SITE IMPROVEMENTS SHOWN HEREIN SHALL BE IN ACCORDANCE WITH:
  - A) CURRENT PREVAILING MUNICIPAL AND/OR COUNTY SPECIFICATIONS, STANDARDS AND REQUIREMENTS

### GENERAL NOTES CONTINUED

14. B) CURRENT PREVAILING UTILITY COMPANY SPECIFICATIONS, STANDARDS, AND REQUIREMENTS
15. THIS SET OF PLANS HAVE BEEN PREPARED FOR THE PURPOSE OF MUNICIPAL AND AGENCY REVIEW AND APPROVAL. THIS SET OF PLANS SHALL NOT BE UTILIZED AS CONSTRUCTION DRAWINGS UNTIL REVISED TO INDICATE "ISSUED FOR CONSTRUCTION".
16. ALL INFORMATION SHOWN MUST BE CERTIFIED PRIOR TO USE FOR CONSTRUCTION ACTIVITIES.

### ABBREVIATIONS

|      |  |
|------|--|
| AMP  | AMPERE   |
| AC   | ALTERNATING CURRENT                                      |
| AL   | ALUMINUM   |
| AF   | AMP. FRAME   |
| AFF  | ABOVE FINISHED FLOOR                                     |
| AFG  | ABOVE FINISHED GRADE                                     |
| AWG  | AMERICAN WIRE GAUGE                                      |
| C    | CONDUIT ( GENERIC TERM OF RACEWAY, PROVIDE AS SPECIFIED) |
| CB   | COMBINER BOX   |
| CKT  | CIRCUIT  |
| CT   | CURRENT TRANSFORMER                                      |
| CU   | COPPER   |
| DC   | DIRECT CURRENT   |
| DISC | DISCONNECT SWITCH  |
| DWG  | DRAWING  |
| EC   | ELECTRICAL SYSTEM INSTALLER                              |
| EMT  | ELECTRICAL METALLIC TUBING                               |
| FS   | FUSIBLE SWITCH   |
| FU   | FUSE   |
| GND  | GROUND   |
| GFI  | GROUND FAULT INTERRUPTER                                 |
| HZ   | FREQUENCY ( CYCLES PER SECOND)                           |


### ABBREVIATIONS CONTINUED

|        |  |
|--------|--|
| JB     | JUNCTION BOX   |
| KCMIL  | THOUSAND CIRCULAR MILS                                     |
| KVA    | KILO-VOLT AMPERE   |
| KW     | KILO-WATT  |
| KWH    | KILO-WATT HOUR   |
| L      | LINE   |
| MCB    | MAIN CIRCUIT BREAKER                                       |
| MDP    | MAIN DISTRIBUTION PANEL                                    |
| MLO    | MAIN LUG ONLY  |
| MTD    | MOUNTED  |
| MTG    | MOUNTING   |
| N      | NEUTRAL  |
| NEC    | NATIONAL ELECTRICAL CODE                                   |
| NIC    | NOT IN CONTRACT  |
| NO #   | NUMBER   |
| NTS    | NOT TO SCALE   |
| OC     | OVER CURRENT PROTECTION                                    |
| P      | POLE   |
| PB     | PULL BOX   |
| PH Ø   | PHASE  |
| PVC    | POLY-VINYL CHLORIDE CONDUIT                                |
| PWR    | POWER  |
| QTY    | QUANTITY   |
| RGS    | RIGID GALVANIZED STEEL                                     |
| SN     | SOLID NEUTRAL  |
| JSWBD  | SWITCHBOARD  |
| TYP    | TYPICAL  |
| U.O.I. | UNLESS OTHERWISE INDICATED                                 |
| WP     | WEATHERPROOF   |
| XFMR   | TRANSFORMER  |
| +72    | MOUNT 72 INCHES TO BOTTOM OF ABOVE FINISHED FLOOR OR GRADE |


### SHEET INDEX

- PV-1 COVER SHEET W/ SITE INFO & NOTES  
PV-2 ROOF PLAN W/ MODULE LOCATIONS  
PV-3 ELECTRICAL 3 LINE DIAGRAM  
PV-4 SITE PLAN  
AP APPENDIX


NOTES : \*REFER TO MODULE SPECS FOR MODULE DIMENSIONS  
\*DEPICTED MODULES MAY BE PORTRAIT OR LANDSCAPE




ATTACHMENT & CLIP DETAIL  
SCALE: NOT TO SCALE



PV MODULE ATTACHMENT ON ASPHALT SHINGLE ROOF  
SCALE: NOT TO SCALE



HEIGHT FROM GROUND LEVEL TO PEAK OF ROOF  
SCALE: NOT TO SCALE



Issued / Revisions

| R1  | SYSTEM SIZE DECREASE / INVERTER CHANGE / LAYOUT REVISION | 6/5/2017  |
|-----|--|-----------|
| P1  | ISSUED TO TOWNSHIP FOR PERMIT                            | 5/24/2017 |
| NO. | DESCRIPTION  | DATE      |

Project Title:  
  
NADELLA, MICHELLE  
TRINITY ACCT #: 2017-04-135521

Project Address:  
  
146 FERNWOOD TERRACE  
LINDEN, NJ 07036

Drawing Title:  
  
PROPOSED PV SOLAR SYSTEM

| Drawing Information |           |
|---------------------|-----------|
| DRAWING DATE:       | 5/24/2017 |
| DRAWN BY:           | RIOS      |
| REVISED BY:         | DMR       |

| System Information: |                     |
|---------------------|---------------------|
| DC SYSTEM SIZE:     | 6.09kW              |
| AC SYSTEM SIZE:     | 5kW                 |
| TOTAL MODULE COUNT: | 21                  |
| MODULES USED:       | HANWHA 290          |
| MODULE SPEC #:      | Q.PEAK-BLK G4.1 290 |
| UTILITY COMPANY:    | PSE&G               |
| UTILITY ACCT #:     | 7278909902          |
| UTILITY METER #:    | 1614925             |
| DEAL TYPE:          | SUNRUN              |

| Rev. No. | Sheet  |
|----------|--------|
| R1       | PV - 2 |



2211 Allenwood Road  
Wall, New Jersey 07719  
877-797-2978  
www.Trinity-Solar.com

NOTES:

- 1.) ALL EQUIPMENT SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTALLATION INSTRUCTIONS.
- 2.) ARRAY BONDING TO COMPLY WITH MANUFACTURER SPECIFICATION.
- 3.) ALL LOCATIONS ARE APPROXIMATE AND REQUIRE FIELD VERIFICATION.
- 4.) AN AC DISCONNECT SHALL BE GROUPED WITH INVERTER ( S ) NEC 690.13 ( E ) .
- 5.) ALL OUTDOOR EQUIPMENT SHALL BE RAIN TIGHT WITH MINIMUM NEMA 3R RATING.
- 6.) ROOFTOP SOLAR INSTALLATION ONLY PV ARRAY SHALL NOT EXTEND BEYOND THE EXISTING ROOF EDGE.

| ARRAY SCHEDULE                                       |      | SYMBOL LEGEND   |         | PLUMBING SCHEDULE  | EQUIPMENT SCHEDULE |                                  |
|--|------|---|---------|--|--------------------|----------------------------------|
| R1<br>ARRAY ORIENTATION = 126°<br>MODULE PITCH = 35° | (R1) | INDICATES ROOF DESIGNATION . REFER TO ARRAY SCHEDULE FOR MORE INFORMATION | (UD)    | INDICATES NEW UTILITY DISCONNECT TO BE INSTALLED OUTSIDE   | QTY                | SPEC #                           |
|  |      |   |         |  | 21                 | HANWHA 290 (Q.PEAK-BLK G4.1 290) |
| R2<br>ARRAY ORIENTATION = 306°<br>MODULE PITCH = 35° | (M)  | INDICATES EXISTING METER LOCATION   | (EP)    | INDICATES NEW PV SOLAR MODULE. <b>RED</b> MODULES INDICATE PANELS THAT USE MICRO INVERTERS. REFER TO EQUIPMENT SCHEDULE FOR SPECS. | 1                  | SE5000A-US                       |
|  |      |   |         |  | OTHER OBSTRUCTIONS |                                  |
|  |      |   |         |  |                    |                                  |
|  | (EP) | INDICATES EXISTING ELECTRICAL PANEL LOCATION: BASEMENT                    | (P)     | INDICATES NEW PRODUCTION METER TO BE INSTALLED OUTSIDE.  |                    |                                  |
|  |      |   |         |  |                    |                                  |
|  | (D)  | INDICATES NEW MAIN DISCONNECT   | (DC/AC) | INDICATES NEW INVERTER TO BE INSTALLED OUTSIDE. REFER TO EQUIPMENT SCHEDULE FOR SPECS.   |                    |                                  |
|  |      |   |         |  |                    |                                  |

ARRAY CIRCUIT WIRING NOTES

1.) LICENSED ELECTRICIAN ASSUMES ALL RESPONSIBILITY FOR DETERMINING ONSITE CONDITIONS AND EXECUTING INSTALLATION IN ACCORDANCE WITH NEC 2014

2.) LOWEST EXPECTED AMBIENT TEMPERATURE BASED ON ASHRAE MINIMUM MEAN EXTREME DRY BULB TEMPERATURE FOR ASHRAE LOCATION MOST SIMILAR TO INSTALLATION LOCATION. LOWEST EXPECTED AMBIENT TEMP = -16°C

3.) HIGHEST CONTINUOUS AMBIENT TEMPERATURE BASED ON ASHRAE HIGHEST MONTH 2% DRY BULB TEMPERATURE FOR ASHRAE LOCATION MOST SIMILAR TO INSTALLATION LOCATION. HIGHEST CONTINUOUS TEMP = 33°C

4.) 2005 ASHRAE FUNDAMENTALS 2% DESIGN TEMPERATURES DO NOT EXCEED 47°C IN THE UNITED STATES (PALM SPRINGS, CA IS 44.1°C). FOR LESS THAN 9 CURRENT-CARRYING CONDUCTORS IN A ROOF-MOUNTED SUNLIT CONDUIT AT LEAST 0.5" ABOVE ROOF AND USING THE OUTDOOR DESIGN TEMPERATURE OF 47°C OR LESS (ALL OF UNITED STATES)

5.) PV SYSTEM CIRCUITS INSTALLED ON OR IN BUILDINGS SHALL INCLUDE A RAPID SHUTDOWN FUNCTION THAT CONTROLS SPECIFIC CONDUCTORS IN ACCORDANCE WITH NEC 690.12(1) THROUGH (5)

6.) PHOTOVOLTAIC POWER SYSTEMS SHALL BE PERMITTED TO OPERATE WITH UNGROUNDED PHOTOVOLTAIC SOURCE AND OUTPUT CIRCUIT AS PER **NEC 690.35**

7.) UNGROUNDED DC CIRCUIT CONDUCTORS SHALL BE IDENTIFIED WITH THE FOLLOWING OUTER FINISH:  
POSITIVE CONDUCTORS = RED  
NEGATIVE CONDUCTORS = BLACK  
**NEC 210.5(C)(2)**

8.) ARRAY AND SUB ARRAY CONDUCTORS SHALL BE #10 PV WIRE TYPE RHW-2 OR EQUIVELANT AND SHALL BE PROTECTED BY CONDUIT WHERE EXPOSED TO DIRECT SUNLIGHT. SUB ARRAY CONDUIT LONGER THAN 24" SHALL CONTAIN ≤ 20 CURRENT CARRYING CONDUCTORS AND WHERE EXPOSED TO DIRECT SUNLIGHT SHALL CONTAIN ≤ 9 CURRENT CARRYING CONDUCTORS.

9.) ALL WIRE LENGTHS SHALL BE LESS THAN 100' UNLESS OTHERWISE NOTED

10.) FLEXIBLE CONDUIT SHALL NOT BE INSTALLED ON ROOFTOP AND SHALL BE LIMITED TO 12" IF USED OUTDOORS

11.) OVERCURRENT PROTECTION FOR CONDUCTORS CONNECTED TO THE SUPPLY SIDE OF A SERVICE SHALL BE LOCATED WITHIN 10' OF THE POINT OF CONNECTION NEC 705.31

12.) WHERE TWO SOURCES FEED A BUSSBAR, ONE A UTILITY AND THE OTHER AN INVERTER, PV BACKFEED BREAKER(S) SHALL BE LOCATED OPPOSITE FROM UTILITY **NEC 705.12(D)(2)(3)(b)**

13.) ALL SOLAR SYSTEM LOAD CENTERS TO CONTAIN ONLY GENERATION CIRCUITS AND NO UNUSED POSITIONS OR LOADS

14.) ALL EQUIPMENT INSTALLED OUTDOORS SHALL HAVE A **NEMA 3R** RATING

**CALCULATIONS FOR CURRENT CARRYING CONDUCTORS**  
REQUIRED CONDUCTOR AMPACITY PER STRING  
[**NEC 690.8(B)(1)**]:  $(15.00 \times 1.25)1 = 18.75A$

AWG #10, DERATED AMPACITY  
AMBIENT TEMP: 33°C, TEMP DERATING FACTOR: .96  
RACEWAY DERATING = 4 CCC: 0.80  
 $(40 \times .96)0.80 = 30.72A$

$30.72A \geq 18.75A$ , THEREFORE WIRE SIZE IS VALID


TOTAL AC REQUIRED CONDUCTOR AMPACITY  
 $21.00A \times 1.25 = 26.25A$

AWG #10, DERATED AMPACITY  
AMBIENT TEMP: 30°C, TEMP DERATING: 1.0  
RACEWAY DERATING ≤ 3 CCC: N/A  
 $40A \times 1.0 = 40A$

$40A \geq 26.25A$ , THEREFORE AC WIRE SIZE IS VALID

**CALCULATION FOR PV OVERCURRENT PROTECTION**  
TOTAL INVERTER CURRENT: 21.00A  
 $21.00A \times 1.25 = 26.25A$   
--> 30A OVERCURRENT PROTECTION IS VALID

|   |
|---|
| SOLAR MODULES MOUNTED TO ROOF ON 2 ARRAYS<br>21 - 290W MODULES W/ 1 SOLAR EDGE P300 PER MODULE<br>15 ADC MAX PER STRING                                 |
| 1 STRING OF 11 MODULES IN SERIES - 350 Vmax<br>1 STRING OF 10 MODULES IN SERIES - 350 Vmax<br>*2 STRINGS TO BE TERMINATED IN PARALLEL INSIDE INVERTER 1 |




| PV MODULE SPECIFICATIONS         |       |
|----------------------------------|-------|
| HANWHA 290 (Q.PEAK-BLK G4.1 290) |       |
| I <sub>mp</sub>                  | 9.07  |
| V <sub>mp</sub>                  | 31.96 |
| V <sub>oc</sub>                  | 39.19 |
| I <sub>sc</sub>                  | 9.56  |

| INVERTER #1 - SE5000A-US |      |                     |       |
|--------------------------|------|---------------------|-------|
| DC                       |      | AC                  |       |
| I <sub>mp</sub>          | 15.5 | P <sub>out</sub>    | 5000  |
| V <sub>mp</sub>          | 350  | I <sub>max</sub>    | 21    |
| V <sub>oc</sub>          | 500  | OCPD <sub>min</sub> | 26.25 |
| I <sub>sc</sub>          | 30   | V <sub>nom</sub>    | 240   |

**NOTE: CONDUIT TYPE SHALL BE CHOSEN BY THE INSTALLATION CONTRACTOR TO MEET OR EXCEED NEC AND LOCAL AHJD REQUIREMENTS**

|   |  |
|---|--|
| A | #6 THWN-2 GEC TO EXISTING GROUND ROD                   |
| B | 3/4" CONDUIT W/ 3-#10 THWN-2, 1-#10 THWN-2 GROUND      |
| C | 3/4" CONDUIT W/ 4-#10 THWN-2, 1-#10 THWN-2 GROUND      |
| D | 3/4" CONDUIT W/ 4-#10 THWN-2, 1-#10 THWN-2 GROUND      |
| E | 3/4" CONDUIT W/ 3-#10 THWN-2, 1-#10 THWN-2 GROUND      |
| F | #10 PV WIRE (FREE AIR) W/ #6 BARE COPPER BOND TO ARRAY |
| G | 3/4" CONDUIT W/ 3-#6 THWN-2, 1-#8 THWN-2 GROUND        |

Engineer / License Holder:



Issued / Revisions

| NO. | DESCRIPTION  | DATE      |
|-----|--|-----------|
| R1  | SYSTEM SIZE DECREASE / INVERTER CHANGE / LAYOUT REVISION | 6/5/2017  |
| P1  | ISSUED TO TOWNSHIP FOR PERMIT                            | 5/24/2017 |

Project Title:

NADELLA, MICHELLE

TRINITY ACCT #: 2017-04-135521

Project Address:

146 FERNWOOD TERRACE  
LINDEN, NJ 07036

Drawing Title:

PROPOSED PV SOLAR SYSTEM

Drawing Information

|               |           |
|---------------|-----------|
| DRAWING DATE: | 5/24/2017 |
| DRAWN BY:     | RIOS      |
| REVISED BY:   | DMR       |

System Information:

|                     |                     |
|---------------------|---------------------|
| DC SYSTEM SIZE:     | 6.09kW              |
| AC SYSTEM SIZE:     | 5kW                 |
| TOTAL MODULE COUNT: | 21                  |
| MODULES USED:       | HANWHA 290          |
| MODULE SPEC #:      | Q.PEAK-BLK G4.1 290 |
| UTILITY COMPANY:    | PSE&G               |
| UTILITY ACCT #:     | 7278909902          |
| UTILITY METER #:    | 1614925             |
| DEAL TYPE:          | SUNRUN              |

Rev. No.

R1



Sheet

PV - 3



2211 Allenwood Road  
Wall, New Jersey 07719

877-797-2978  
www.Trinity-Solar.com



Issued / Revisions

| NO. | DESCRIPTION  | DATE      |
|-----|--|-----------|
| R1  | SYSTEM SIZE DECREASE / INVERTER CHANGE / LAYOUT REVISION | 6/5/2017  |
| P1  | ISSUED TO TOWNSHIP FOR PERMIT                            | 5/24/2017 |

Project Title:  
NADELLA, MICHELLE  
TRINITY ACCT #: 2017-04-135521

Project Address:  
146 FERNWOOD TERRACE  
LINDEN, NJ 07036

Drawing Title:  
PROPOSED PV SOLAR SYSTEM

| Drawing Information |           |
|---------------------|-----------|
| DRAWING DATE:       | 5/24/2017 |
| DRAWN BY:           | RIOS      |
| REVISED BY:         | DMR       |

| System Information: |                     |
|---------------------|---------------------|
| DC SYSTEM SIZE:     | 6.09kW              |
| AC SYSTEM SIZE:     | 5kW                 |
| TOTAL MODULE COUNT: | 21                  |
| MODULES USED:       | HANWHA 290          |
| MODULE SPEC #:      | Q.PEAK-BLK G4.1 290 |
| UTILITY COMPANY:    | PSE&G               |
| UTILITY ACCT #:     | 7278909902          |
| UTILITY METER #:    | 1614925             |
| DEAL TYPE:          | SUNRUN              |

| Rev. No. | Sheet  |
|----------|--------|
| R1       | PV - 4 |

